RATING	Securement	Deck	Max. Slope	Application	Membrane	Membrane Attachment	Cover Board	Cover Board Attachment	Insulation	Insulation Attachment	Vapor Barrier	Thermal Barrier	RoofNav Assembly #
1B-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	0.5" IKOTherm CoverShield or Securock Gypsum Fiber Roof Board	InnoviFast Insulation Fasteners and Insulation Plates, 16 per 4' x 8' board	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	Through-fastened	(OPTIONAL) min. 4-mil poly, through-fastened, **OR** ArmourGard-A Vapour Retarder, through-fastened, **OR** IKO MVP or MVP Sand adhered to thermal barrier (optional InnoviBond Membrane Adhesive SPR)	(OPTIONAL) 0.5" DensDeck, DensDeck Prime, Securock Gypsum-Fiber, through-fastened	553972-0-0
1B-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.5	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive SPR	0.5" IKOTherm CoverShield or Securock Gypsum Fiber Roof Board	InnoviFast Insulation Fasteners and Insulation Plates, 16 per 4' x 8' board	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	Through-fastened	(OPTIONAL) min. 4-mil poly, through-fastened, **OR** ArmourGard-A Vapour Retarder, through-fastened, **OR** IKO MVP or MVP Sand adhered to thermal barrier (optional InnoviBond Membrane Adhesive SPR)	(OPTIONAL) 0.5" DensDeck, DensDeck Prime, Securock Gypsum-Fiber, through-fastened	553973-0-0
1C-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	0.5" IKOTherm CoverShield or Securock Gypsum Fiber Roof Board	InnoviFast Insulation Fasteners and Insulation Plates, 16 per 4' x 8' board	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	Through-fastened	(OPTIONAL) min. 4-mil poly, through-fastened, **OR** ArmourGard-A Vapour Retarder, through-fastened, **OR** IKO MVP or MVP Sand adhered to thermal barrier (optional InnoviBond Membrane Adhesive SPR)	(OPTIONAL) 0.5" DensDeck, DensDeck Prime, Securock Gypsum-Fiber, through-fastened	553974-0-0
1B-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	N/A	N/A	Min. 2.0" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	InnoviFast Insulation Fasteners and Insulation Plates, 16 per 4' x 8' board	(OPTIONAL) min. 4-mil poly, through-fastened, **OR** ArmourGard-A Vapour Retarder, through-fastened, **OR** IKO MVP or MVP Sand adhered to thermal barrier (optional InnoviBond Membrane Adhesive SPR)	(OPTIONAL) 0.5" DensDeck, DensDeck Prime, DEXcell Cement Roof Board, DEXcell FA Glass Mat, DEXcell Glass Mat Roof Board, Securock Gypsum-Fiber, through-fastened	554050-0-0
1B-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.5	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive SPR	N/A	N/A	Min. 2.0" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	InnoviFast Insulation Fasteners and Insulation Plates, 16 per 4' x 8' board	(OPTIONAL) min. 4-mil poly, through-fastened, **OR** ArmourGard-A Vapour Retarder, through-fastened, **OR** IKO MVP or MVP Sand adhered to thermal barrier (optional InnoviBond Membrane Adhesive SPR)	(OPTIONAL) 0.5" DensDeck, DensDeck Prime, DEXcell Cement Roof Board, DEXcell FA Glass Mat, DEXcell Glass Mat Roof Board, Securock Gypsum-Fiber, through-fastened	554051-0-0
1C-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	N/A	N/A	Min. 2.0" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	InnoviFast Insulation Fasteners and Insulation Plates, 16 per 4' x 8' board	(OPTIONAL) min. 4-mil poly, through-fastened, **OR** ArmourGard-A Vapour Retarder, through-fastened, **OR** IKO MVP or MVP Sand adhered to thermal barrier (optional InnoviBond Membrane Adhesive SPR)	(OPTIONAL) 0.5" DensDeck, DensDeck Prime, DEXcell Cement Roof Board, DEXcell FA Glass Mat, DEXcell Glass Mat Roof Board, Securock Gypsum-Fiber, through-fastened	554052-0-0
1B-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	N/A	N/A	**Top Layer:** Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III **Bottom Layer:** Min. 2.0" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	**Top Layer:** Millennium Adhesive, 12.0" o.c. Row Spacing **Bottom Layer:** InnoviFast Insulation Fasteners and Insulation Plates, 16 per 4' x 8' board	(OPTIONAL) min. 4-mil poly, through-fastened, **OR** ArmourGard-A Vapour Retarder, through-fastened, **OR** IKO MVP or MVP Sand adhered to thermal barrier (optional InnoviBond Membrane Adhesive SPR)	(OPTIONAL) 0.5" DensDeck, DensDeck Prime, DEXcell Cement Roof Board, DEXcell FA Glass Mat, DEXcell Glass Mat Roof Board, Securock Gypsum-Fiber, through-fastened	554053-0-0
1B-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.5	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive SPR	N/A	N/A	**Top Layer:** Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III **Bottom Layer:** Min. 2.0" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	**Top Layer:** IKO Millennium Adhesive, 12.0" o.c. Row Spacing **Bottom Layer:** InnoviFast Insulation Fasteners and Insulation Plates, 16 per 4' x 8' board	(OPTIONAL) min. 4-mil poly, through-fastened, **OR** ArmourGard-A Vapour Retarder, through-fastened, **OR** IKO MVP or MVP Sand adhered to thermal barrier (optional InnoviBond Membrane Adhesive SPR)	(OPTIONAL) 0.5" DensDeck, DensDeck Prime, DEXcell Cement Roof Board, DEXcell FA Glass Mat, DEXcell Glass Mat Roof Board, Securock Gypsum-Fiber, through-fastened	554054-0-0
1C-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	N/A	N/A	**Top Layer:** Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III **Bottom Layer:** Min. 2.0" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	**Top Layer:** IKO Millennium Adhesive, 12.0" o.c. Row Spacing **Bottom Layer:** InnoviFast Insulation Fasteners and Insulation Plates, 16 per 4' x 8' board	(OPTIONAL) min. 4-mil poly, through-fastened, **OR** ArmourGard-A Vapour Retarder, through-fastened, **OR** IKO MVP or MVP Sand adhered to thermal barrier (optional InnoviBond Membrane Adhesive SPR)	(OPTIONAL) 0.5" DensDeck, DensDeck Prime, DEXcell Cement Roof Board, DEXcell FA Glass Mat, DEXcell Glass Mat Roof Board, Securock Gypsum-Fiber, through-fastened	554055-0-0
1C-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	0.5" IKOTherm CoverShield or DensDeck Prime	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP adhered to thermal barrier with InnoviBond Membrane Adhesive SPR	0.5" Densdeck Prime or Securock Gypsum-Fiber Roof Board, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 12 per 4' x 8' Board	554056-0-0
1C-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	0.5" DensDeck Prime	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP Sand adhered to thermal barrier primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum-Fiber Roof Board, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 12 per 4' x 8' Board	554113-0-0
1C-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	0.5" IKOTherm CoverShield	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP adhered to thermal barrier primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum-Fiber Roof Board, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 12 per 4' x 8' Board	554114-0-0
1B-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	0.5" IKOTherm CoverShield	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP adhered to thermal barrier primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum-Fiber Roof Board, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 12 per 4' x 8' Board	554115-0-0
1C-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	0.5" IKOTherm CoverShield	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP Sand adhered to thermal barrier primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum-Fiber Roof Board, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 12 per 4' x 8' Board	554116-0-0
1B-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	0.5" IKOTherm CoverShield	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP Sand adhered to thermal barrier primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum-Fiber Roof Board, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 12 per 4' x 8' Board	554117-0-0
1B-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.5	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive SPR	0.5" IKOTherm CoverShield	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP Sand adhered to thermal barrier primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum-Fiber Roof Board, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 12 per 4' x 8' Board	554118-0-0
1B-90, SH	**Adhered**	22 to 16 ga, 33ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	0.5" Securock Gypsum-Fiber Roof Board	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP or IKO MVP Sand adherd to thermal barrier primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum-Fiber Roof Board, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 12 per 4' x 8' Board	554119-0-0

1C-135, SH	**Adhered**	22 to 18 ga, 33 ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	N/A	N/A	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP, primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum-Fiber, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 16 per 4' x 8' Board	554120-0-0
1B-135, SH	**Adhered**	22 to 18 ga, 33 ksi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	N/A	N/A	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP or IKO MVP Sand, primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum-Fiber, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 16 per 4' x 8' Board	554121-0-0
1B-135, SH	**Adhered**	22 to 18 ga, 33 ksi	0.5	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive SPR	N/A	N/A	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP or IKO MVP Sand, primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum-Fiber, fastened with InnoviFast Insulation Fasteners and InnoviFast Insulation Plates, 16 per 4' x 8' Board	554121-0-0
NC, C-165, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	0.5" IKOTherm CoverShield/IKOTherm-A CoverShield or DensDeck or DensDeck Prime or Securock Gypsum Fiber Roof Board	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP, primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck or DensDeck Prime or Securock Gypsum-Fiber, adhered with IKO Millennium Adhesive, 12.0" o.c. Row Spacing	554125-0-0
NC, C-165, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	0.5" IKOTherm CoverShield/IKOTherm-A CoverShield or DensDeck or DensDeck Prime or Securock Gypsum Fiber Roof Board	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP Sand, primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck or DensDeck Prime or Securock Gypsum-Fiber, adhered with IKO Millennium Adhesive, 12.0" o.c. Row Spacing	554126-0-0
NC, B-165, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	0.5" IKOTherm CoverShield/IKOTherm-A CoverShield or DensDeck or DensDeck Prime or Securock Gypsum Fiber Roof Board	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP, primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck or DensDeck Prime or Securock Gypsum-Fiber, adhered with IKO Millennium Adhesive, 12.0" o.c. Row Spacing	554128-0-0
NC, B-165, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	0.5" IKOTherm CoverShield/IKOTherm-A CoverShield or DensDeck or DensDeck Prime or Securock Gypsum Fiber Roof Board	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP Sand, primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck or DensDeck Prime or Securock Gypsum-Fiber, adhered with IKO Millennium Adhesive, 12.0" o.c. Row Spacing	554129-0-0
NC, B-165, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.5	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive SPR	0.5" IKOTherm CoverShield/IKOTherm-A CoverShield or DensDeck or DensDeck Prime or Securock Gypsum Fiber Roof Board	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP, primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck or DensDeck Prime or Securock Gypsum-Fiber, adhered with IKO Millennium Adhesive, 12.0" o.c. Row Spacing	554130-0-0
NC, B-165, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.5	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive SPR	0.5" IKOTherm CoverShield/IKOTherm-A CoverShield or DensDeck or DensDeck Prime or Securock Gypsum Fiber Roof Board	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP Sand, primed with InnoviBond Membrane Adhesive SPR	0.5" DensDeck or DensDeck Prime or Securock Gypsum-Fiber, adhered with IKO Millennium Adhesive, 12.0" o.c. Row Spacing	554131-0-0
NC, C-210, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	0.5" DensDeck Prime or Securock Gypsum Fiber Roof Board	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP, primed with InnoviBond Membrane Adhesive SPR	N/A	554135-0-0
NC, B-210, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	0.5" DensDeck Prime or Securock Gypsum Fiber Roof Board	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP, primed with InnoviBond Membrane Adhesive SPR	N/A	554136-0-0
NC, B-210, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.5	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive SPR	0.5" DensDeck Prime or Securock Gypsum Fiber Roof Board	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	Min. 1.5" IKOTherm III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	IKO MVP, primed with InnoviBond Membrane Adhesive SPR	N/A	554137-0-0
NC, C-525, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive	N/A	N/A	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	N/A	N/A	554132-0-0
NC, B-525, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.25	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive LVOC	N/A	N/A	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	N/A	N/A	554133-0-0
NC, B-525, SH	**Adhered**	min 2"-thick Structural Concrete, 2500 psi	0.5	New Roof	IKO Innovi TPO, any thickness, any width	InnoviBond Membrane Adhesive SPR	N/A	N/A	Min. 1.5" IKOTherm/IKOTherm-A or IKOTherm III/IKOTherm-A III	IKO Millennium Adhesive, 12.0" o.c. Row Spacing	N/A	N/A	554134-0-0